



**Contractor**  
George Reed, Inc.

**Funding Source**  
Measure L  
CMAQ  
RTIF

**Construction Cost**  
\$1,616,278.50

Date: 09/13/2019  
Project No. 9727

**Hours**

Monday - Friday  
7:00 am - 5:00 pm



Questions?

(909) 525-4130



## Crows Landing Rd. & Grayson Rd. INTERSECTION IMPROVEMENTS

### About the Project

This intersection will have a traffic signal installed and will be widened to accommodate existing and projected traffic. Northbound Crows Landing Road will be restriped to maintain the current lane configuration of the center left-turn lane and through-right turn lane. The southbound Crows Landing Road will be restriped to maintain the current lane configuration which includes a dedicated right turn pocket, left turn lane, and one through lane. The east and west legs of Grayson Road will be widened to provide a left turn pocket and a through-right lane. The existing left turn pocket on the westbound approach of Grayson Road for access to St. Stan's Golf Course will be restriped. The improved roadway sections will be restriped and signed.

### Project Benefits

- Traffic Safety
- Traffic Flow

### What to Expect During Construction

- Traffic Delays
- Road Closures
- Noise

### Schedule

<u>ESTIMATED START DATE</u>	<u>ESTIMATED COMPLETION DATE</u>
August 19, 2019	November 30, 2019